Mobile: 0450 800 006 | Office: (02) 8033 6874
info@dlcivil.com.au | dlcivil.com.au

HEAVY IRON | SURGICAL PRECISION | ZERO PROGRAM DELAYS

Sydney Civil Construction, Excavation, Rock Sawing & Wet Hire

Founded by David Leonard and operating from our dedicated fleet yard at **3 Anderson St, Banksmeadow NSW 2019**, DL Civil Pty Ltd is an owned-fleet civil construction and excavation contractor servicing commercial builders, property developers, councils, pool builders, and residential projects across Greater Sydney.

1.7t - 38t
Owned Excavators & Topcon GPS

~980mm
Removable-Cab Tight Access

Banksmeadow
Rapid Yard & Float Mobilisation

Tier-1 WHS
VOC Operators & EPA Dockets





CORE CAPABILITIES (5 SPECIALIST DISCIPLINES)

01. Civil Construction & Infrastructure

- Stormwater drainage, pits, culverts & OSD tank excavations
- Commercial car park subgrades & AUS-SPEC kerb preparation
- BYDA service locating, Sydney Water Peg-Out & AS 3798 compaction

02. Bulk & Detailed Excavation

- Multi-level bulk basements (30t - 38t Kobelco + Topcon GPS)
- Detailed pad/strip footings, lift overruns & underpinning prep
- Underground enclosed-cab & 1.7t removable-cab tight-access digs

03. Demolition & Site Remediation

- Controlled residential, commercial & structural demolition
- Reinforced slab breakout & 100% concrete/brick recycling diversion
- NSW EPA VENM/ENM vs GSW/RSW/GSW-A segregation & LAA coordination

04 & 05. Pool Excavation & Rock Sawing

- Low-vibration diamond rock sawing (DIN 4150-3 boundary control)
- Silenced hydraulic hammering, rotary rock grinding & wet dust control
- Precision concrete & fibreglass pool shells with driveway protection

OPERATIONAL DELIVERY SEQUENCE

STEP 01 | STEP 02 | STEP 03 | STEP 04

OWNED WET-HIRE FLEET & DIMENSIONAL SCHEDULE (15 MACHINE CLASSES)

MACHINE CLASS	WIDTH / PAYLOAD	MAX DEPTH / CAP	PRIMARY SYDNEY APPLICATION
1.7t Yanmar Excavator	980mm - 1.28m (Removable Cab)	~2.3m depth	Narrow Sydney terrace passages, indoor strip-outs & under-house digs
3.5t Hitachi Excavator	~1.55m (Zero-Swing)	~3.1m depth	Backyard pool excavations, retaining wall footings & driveways
5.5t Yanmar Excavator	~1.97m	~3.8m depth	Urban civil trenches, diamond rock sawing, hammers & augers
8t Excavator	~2.28m	~4.5m depth	Mid-size urban civil, sandstone sawing & heavy hammering
14.5t Case Excavator	~2.49m (Short-Radius)	~5.5m depth	Commercial basements, deep stormwater, rock sawing & bogie loading
20t Excavator	~2.80m	~6.5m depth	Multi-res bulk earthworks, structural demolition & heavy breaking
30t Kobelco SK300	30T Heavy (Enclosed Cab)	~7.2m depth	High-production commercial bulk load-ups & deep basements
36t - 38t Kobelco (Topcon GPS)	36T - 38T (Enclosed Cab)	~7.5m depth	Flagship bulk excavation with Topcon GPS grade control & heavy rock
Kubota SVL75 Posi Track	~1.72m (High-Flow)	4-in-1 / Forks	Basement load-outs, final trim, pallet handling & site sweeping
3t / 6t / 8t Rigid Tippers	3.0t / 6.0t / 8.0t Payload	2.5 - 6.0 m3	Narrow Inner West laneways, steep drives & suburban spoil cartage
6x4 Bogie (10-Wheeler)	~12.5t NSW GVM Cap	7.5 - 9.5 m3	Continuous commercial bulk spoil haulage & DGB20 deliveries
Isuzu Beavertail & Tilt-Tray	Hydraulic Ramps / Tilt	1.7t - 14.5t plant	In-house rapid mobilisation & attachment swaps (20t-38t via low-loader)

IN-HOUSE HYDRAULIC ATTACHMENTS & GRADE CONTROL

ATTACHMENT	CARRIERS	COMPLIANCE & SITE BENEFIT
Hydraulic Diamond Rock Saws	5.5t to 38t Excavators	Low-vibration boundary relief cuts (DIN 4150-3) with wet silica suppression
Silenced Rock Hammers & Grinders	1.7t to 38t Excavators	Controlled sandstone breakout & millimetre basement face profiling
Augers, Grabs & Compaction Wheels	1.7t to 38t Excavators	Pier holes, demolition waste segregation & trench compaction
Topcon GPS & Laser Systems	38t Kobelco & Site Crew	Verified survey RL levels reducing concrete over-pour and rework

WHS GOVERNANCE, INSURANCES & COMMERCIAL PRE-QUALIFICATION